



Modular Pipe Rack System & Pipe

SCOPE OF SERVICES

Summit Metal Fabricators was contracted to fabricate a modular pipe rack designed to be portable and adjustable for use in a large processing facility.

PROJECT HIGHLIGHTS

Summit fabricated, assembled and installed five (5) modules measuring twelve (12) feet high by eight (8) feet wide in various lengths totaling 130 feet. The modules are comprised of multiple levels utilizing one and a half (1.5) inch to four (4) inch ductile Iron and PVC pipe. The module units were fabricated and assembled in New Hampshire and then shipped out of state. The assembled modules were pressure tested before shipping, and all of the modules were either galvanized or epoxy painted.



MODULAR PIPE RACK SYSTEM

VARIOUS LOCATIONS

SUMMIT METAL FABRICATORS