View more project photos on our website
www.methuenconstruction.com

SESD PRIMARY CLARIFIERS - SALEM, MA

PROJECT INFO:

OWNER:
South Essex Sewerage District

ENGINEER:
AECOM

PROJECT VALUE:
$10 Million

TECHNOLOGIES/MATERIALS:
Sludge Collection Equipment-Chain and Flight

PROJECT HIGHLIGHTS:
This project restores seven primary clarifier tanks and primary influent and effluent channels at the SESD WTP.

ADDITIONAL DETAILS

Methuen Construction is restoring seven primary clarifier tanks and primary influent and effluent channels at the South Essex Sewerage District's Wastewater Treatment Plan in Salem, MA. The work consists of removal, rehabilitation and reinstallation of sludge collections equipment, concrete and metallic surface preparation, repair and resurfacing, protective lining work including lining system termination, environmental controls and proper disposal of all debris, and appurtenant and related work.